Decent Decor Private Limited

Plot No.- 21, Tejaswini Society, Lane No- 1, DP Road, Aundh, Pune - 411 007
E-Mail I'D- marketing@decentdecorindia.com
Office Phone- 8956652623
GST No. - 27AAECD7921Q1Z2

To,

Infosys Limited

Phase II, STP UNIT-II, Plot No 24/2, Rajiv Gandhi InfoTech Park, Hinjawadi, Village- Man, Taluka- Mulshi, Pune- 411057. India.

Quotation Date: 14.10.2026
Quotation No: DDPL/Q/26-27/018
Kind Atten:

SUB :-

Sr.	Description of Work / Goods	HSN/SAC	Qty	UOM	Rate/Unit	Total Amount	PO Ref. No.	PO Date
1	Debris shifting outside of the campus	9954	1.00	NO	3,500.00	**3,500.00**	2300258248	21.10.2025
2	"EXTERNAL PLASTERING Providing and applying cement plaster 20 mm thick in double coat to all external surfaces at all heights, base coat with C.M 1 : 4, 12 mm thk and finish coat 8 mm thk. with 1:3 cement mortar including finishing with steel trowel at all levels to correct line, The surface / wall to be plastered shall be free from any dirt, loose material, and grease etc. The plaster shall be carried out on jambs, bands, lintel and sill faces top and undersides etc. inclusive of supplying and fixing of Chicken Mesh made out of Galvanized iron coils of nominal thickness 0.35mm with hot dip zinc coating of 120gms/sqm (minimum 300mm) width at junctions of concrete and brick work prior to plastering etc including tying in position by using suitable nails / clamps / screws at all levels,etc., complete as directed By Engineer In Charge."	9954	1.00	SQM	800.00	**800.00**	2300258740	04.11.2025

Sr.	Description of Work / Goods	HSN/SAC	Qty	UOM	Rate/Unit	Total Amount	PO Ref. No.	PO Date
3	"230 MM THICK BRICK WORK Providing and laying locally available 230mm thick first class brick work with bricks of class designation 3.5 for substructures like retaining walls, walls & footings, partitions, steps, drains, manholes, trenches, inspection chambers etc. with cement mortar 1:4 (or) 1:5 (or) 1:6 of 12mm thick joints at all levels including raking out joints staging scaffolding and curing, etc., with all materials and labour complete.	9954	1.00	Cum	8,500.00	**8,500.00**	2300258740	04.11.2025
4	Labour charges of zari work 100 x 50mm on concreete floor	9954	1.00	RMT	450.00	**450.00**	1200028675	14.07.2022
*	**GST 18 % applicable**							

Amount In Words: **Rupees Thirteen thousand and two hundred and fifty only.**	**Basic Amount :**	**13,250.00**
	Round off (+/-) :	**0.00**
	GRAND TOTAL	**13,250.00**

Terms & Conditions

1. Payment Terms: 40% advance along with PO, 50% during work progress, and 10% within 15 days of invoice submission or as mutually agreed.
2. Quotation Validity: Valid for 2 months from the date of quotation.
3. GST & Taxes: GST and other applicable taxes shall be charged extra, as applicable.
4. Scope & Variation: Any work beyond the mentioned scope/BOQ or changes in specifications/quantities shall be treated as additional work and charged separately with mutual approval.
5. Site Conditions: Rates are based on the site conditions and information available at the time of quotation. Any unforeseen conditions affecting cost or execution shall be mutually discussed and agreed.
6. Client Approvals: Timely approval of drawings, samples, specifications, permits and other required documents shall be provided by the client to avoid delays.
7. Jurisdiction: Any disputes shall be subject to the jurisdiction of Pune courts only.

For Decent Decor Pvt. Ltd.



Authorized Signatory